



- NOTES:**
1. ALL ROOF PENETRATIONS AFTER COMPLETION OF THE SHELL TO BE PERFORMED BY THE ORIGINAL ROOFING CONTRACTOR SO THAT THE ROOF WARRANTY IS NOT AFFECTED.
  2. ALL ROOF TOP UNITS WILL BE INSTALLED UNDER THE UPFIT OF THE SPACE. LOCATIONS SHOWN ARE APPROXIMATE. IF WEIGHTS EXCEED THE ONES SHOWN THE UPFIT DESIGNER TO PROVIDE ADDITIONAL STEEL AS NEEDED.
  3. ANY ANGLE FRAMING NEEDED TO SUPPORT THE METAL DECK AFTER THE EQUIPMENT ARE INSTALLED WILL BE DESIGNED BY THE UPFIT DESIGNER AND PROVIDED BY THE UPFIT CONTRACTOR.
  4. PROVIDE 2'-0" WIDE WALKING PADS TO ALL RTU AND 3'-0" WIDE AROUND ALL UNITS, AFTER UNITS ARE INSTALLED.
  5. PROVIDE TREATED TIMBERS TO CARRY THE CONDENSING UNITS. INSTALL ON DOUBLE ROOFING MEMBRANE AND VIBRATOR ISOLATORS.
  6. ANY REFRIGERANT LINE PENETRATIONS TO BE INSTALLED IN 600SE NECK TYPE PENETRATIONS

NOTE:  
ANY ROOF PENETRATIONS THAT OCCUR AFTER THE ROOF IS COMPLETED AND THE ROOF WARRANTY IS STILL IN AFFECT SHALL BE DONE BY THE ORIGINAL ROOFING CONTRACTOR SO THAT THIS WORK DOES NOT VOID THE ORIGINAL ROOF WARRANTY

101 ROOF PLAN BUILDING A 1/8"=1'-0"

# SAMPLE ONLY

COPYRIGHT BY  
CREATIVE CONCEPTS AND DESIGN, INC.

- PRELIMINARY NOT FOR CONSTRUCTION
- ISSUED FOR BIDDING
- ISSUED FOR PERMIT
- ISSUED FOR CONSTRUCTION

ROOF PLAN  
BUILDING A

Drawn By \_\_\_\_\_  
 Issue Date: \_\_\_\_\_  
 Drawing File Name  
 1412\_A1-4.1\_Roof Plan.dwg  
 Revisions  
 No. \_\_\_\_\_ Date \_\_\_\_\_  
 No. \_\_\_\_\_ Date \_\_\_\_\_  
 No. \_\_\_\_\_ Date \_\_\_\_\_  
 No. \_\_\_\_\_ Date \_\_\_\_\_

Project Number  
**17-13**  
 Building

Sheet \_\_\_\_\_ Of \_\_\_\_\_  
**A1-4.1**

Drawing Status

Owner

Project

Sheet Title